



IFB 2016-0004 - ADDENDUM 1

LEMOYNE AVENUE PROJECT
Town of Hilton Head Island, South Carolina

Date Issued: March 22, 2016

- Item 1. Sealed construction plans dated 3-15-16 were distributed at the pre-bid meeting. These have also been loaded on the Town's web site.
- Item 2. Read-only AutoCAD files of the plans are being provided via e-mail attachment
- Item 3: The required BID BOND shall be 10% of the total bid amount
(for clarification, the 5% discussed at pre-bid meeting was in error)
- Item 4: Pavement base material shall be HMA. GABC has been deleted from the bid schedule. 450 LBS/SY of HMA base course Type B shall be substituted for the 6" GABC shown on the typical sections. A REVISED BID SCHEDULE dated 3-21-16 is attached (PDF and Excel spreadsheet)
- Item 5: Bid all work shown in the plans and specifications. If any work must be deleted due to easements a change order will be issued.
- Item 6: The Town has contracted with Jones Brothers Tree Surgeons to remove trees and grind stumps within the job's clearing limits. All of this cut and ground material will be hauled from the site. The contractor will need to meet the grading and compaction requirements in accordance with the plans and specifications.

ATTACHED:

Reminder: Bid Submittal Deadline is Monday, March 28, 2016 at 3:00 PM

LEMOYNE AVENUE PROJECT EXHIBIT C

LIST OF ESTIMATED QUANTITIES / BID SCHEDULE - IFB 2016-0004

REVISED 03/21/2016

The unit prices given on this document, along with any negotiated changes in quantities, shall become the basis for, and included in, the contract agreement. Bidders are responsible for verifying all quantities and notifying the Owner of any discrepancies greater than 10% of estimate, in writing, prior to the bid opening. These quantities used as the basis for the contract shall superseded the summary of estimated quantities table in the plans.

ITEM NO.	SCDOT SPEC or SPEC PROV	ITEM DESCRIPTION	UNIT	EST. QUANT.	UNIT PRICE	VALUE
1	1031000	MOBILIZATION	LS	NEC.	\$ -	\$ -
2	1050800	CONSTRUCTION STAKES, LINES & GRADES	EA	1	\$ -	\$ -
3	1071000	TRAFFIC CONTROL	LS	NEC	\$ -	\$ -
4	2012000	CLEARING & GRUBBING WITHIN ROADWAY	LS	NEC	\$ -	\$ -
5	2016000	SELECTED REMOVAL OF MARKED TREES	LS	NEC	\$ -	\$ -
6	2024100	REMOVAL & DISPOSAL OF EXISTING CURB	LF	150	\$ -	\$ -
7	2025000	REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT	SY	520	\$ -	\$ -
8	2031000	UNCLASSIFIED EXCAVATION (INCLUDES PONDS)	CY	7160	\$ -	\$ -
9	2103000	FLOWABLE FILL	CY	15	\$ -	\$ -
10	3100320	HOT MIX ASPHALT BASE COURSE - TYPE B	TON	200	\$ -	\$ -
11	4011004	LIQUID ASPHALT BINDER PG64-22	TON	80	\$ -	\$ -
12	4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	SY	700	\$ -	\$ -
13	4030340	HOT MIX ASPHALT SURFACE COURSE TYPE C or CM	TON	1165	\$ -	\$ -
14	6020005	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF	304	\$ -	\$ -
15	6271020	12" WHITE SOLID LINES - THERMO. - 125 MIL	LF	60	\$ -	\$ -
16	6271010	4" WHITE SOLID LINES (PVT. EDGE LINES) THERMO.- 90 MIL.	LF	2460	\$ -	\$ -
17	6271025	24" WHITE SOLID LINES (STOP/DIAG LINES)-THERMO.-125 MIL	LF	125	\$ -	\$ -
18	6271030	WHITE SINGLE ARROWS (LT, STRGHT, RT) THERMO.-125 MIL	EA	2	\$ -	\$ -
19	6271050	HANDICAP SYMBOL - THERMOPLASTIC - 125 MIL.	EA	1	\$ -	\$ -
20	6271074	4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO-90 MIL.	LF	2360	\$ -	\$ -
21	6510105	FLAT SHEET, TYPE III, FIXED SZ. & MSG. SIGN	SF	44.00	\$ -	\$ -
22	6531210	U-SECTION POST FOR SIGN SUPPORTS - 3P	LF	100	\$ -	\$ -
23	7141141	14"X 23" HORIZONTAL ELLIPTICAL(HE) RC PIPE CUL.-CLASS HE-III	LF	90	\$ -	\$ -
24	7141112	15" RC PIPE CUL.-CLASS III	LF	670	\$ -	\$ -
25	7141113	18" RC PIPE CUL.-CLASS III	LF	152	\$ -	\$ -
26	7141114	24" RC PIPE CUL.-CLASS III	LF	32	\$ -	\$ -
27	7191250	CATCH BASIN -TYPE 9 MH (POND OUTLET STRUCTURES)	EA	2	\$ -	\$ -
28	7192020	DROP INLET(24" X 36")	EA	5	\$ -	\$ -
29	7192105	MANHOLE	EA	2	\$ -	\$ -
30	7192260	48" X 48" JUNCTION BOX	EA	1	\$ -	\$ -
31	719228Z	JUNCTION BOX (SPECIAL)	EA	1	\$ -	\$ -
32	7197120	ADJUST EXISTING MANHOLE TOPS	LS	NEC	\$ -	\$ -
33	7197141	ADJUST UTILITY VALVE BOX COVERS	LS	NEC	\$ -	\$ -
34	7198420	MANHOLE - CONVERT EXISTING DROP INLET 24"X 36"	EA	1	\$ -	\$ -
25	7198530	DROP INLET 24" X 36" - CONVERT EXISTING CATCH BASIN (ROOF/GRA	EA	2	\$ -	\$ -
26	7207001	CONCRETE FLUME (AT BIO-SWALE)	EA	4	\$ -	\$ -
27	7203110	CONCRETE CURB AND GUTTER(1'-6") VERTICAL FACE	LF	280	\$ -	\$ -
28	7204100	CONCRETE FOR APRONS AT CROSSWALKS (4" UNIFORM)	SY	25	\$ -	\$ -
29	7204900	DETECTABLE WARNING SURFACE	SF	45	\$ -	\$ -
40	8072000	RESET CHAIN LINK FENCE	LF	65	\$ -	\$ -
41	8114011	TREE PROTECTION	LS	NEC	\$ -	\$ -
42	8132000	SODDING - CENTIPEDE GRASS	SY	15	\$ -	\$ -
43	8151110	TEMP. EROSION CONTROL BLANKET	MSY	1.135	\$ -	\$ -
44	8151101	TURF REINFORCEMENT MATTING (TRM) TYPE 1	MSY	0.113	\$ -	\$ -
45	8152004	INLET STRUCTURE FILTER - TYPE F (WEIGHTED)	LF	150	\$ -	\$ -
46	8152007	SEDIMENT TUBES FOR DITCH CHECKS	LF	40	\$ -	\$ -
47	8152006	INLET STRUCTURE FILTER- TYPE F (NON-WEIGHTED)	LF	150	\$ -	\$ -
48	8153000	SILT FENCE	LF	300	\$ -	\$ -
49	DETAIL	GRAVEL FILTER RING AT OUTLET STRUCTURES	EA	2	\$ -	\$ -
50	DETAIL	GRAVEL FILTER UNDER ELLIPTICAL PIPES - #57 STONE	TN	48	\$ -	\$ -
51	DETAIL	FILTER FABRIC FOR GRAVEL UNDER ELLIPTICAL PIPES (MIRAFI 140N)	SF	1180	\$ -	\$ -
52	DETAIL	FLARED END SECTION (GEORGIA DOT)	EA	3	\$ -	\$ -
53	DETAIL	CONCRETE WHEEL STOPS	EA	12	\$ -	\$ -
54	SPECIAL	RECONSTR. ASPHALT FOR REPLACEMENT OF EXIST. RCP	LS	NEC	\$ -	\$ -
55	DETAIL	REMOVAL AND RELOCTION OF EXISTING PATHWAY SIGNS	LS	NEC	\$ -	\$ -
56	SP-1	RELOCATION OF EXISTING RR TIE WALLS	LF	100	\$ -	\$ -
57	SP-2	NEW MORTARLESS BLOCK RETAINING WALLS	LF	180	\$ -	\$ -
58	SP-3	TRAFFIC PATTERN XD IMPRINTED CROSSWALK	SF	260	\$ -	\$ -
					TOTAL	\$ -